

ESCRI-SA KNOWLEDGE SHARING

Second Workshop

8 May 2018



HIGH VOLTAGE SOLUTIONS...

Agenda


- › Welcome – Introduce CPP and ABB
- › Construction Video
- › Knowledge Sharing – CPP and ABB
- › CPP: Key Achievements
- › CPP: Installation Testing and Commissioning Challenges
- › ABB: Modelling
- › ABB: Testing
- › ABB: Knowledge Sharing Portal
- › ABB: Custom Training Packages



Design Installation and Commissioning Challenges - Video



Dalrymple North Site – As Designed



Dalrymple North Substation – As Constructed



Key Installation and Commissioning Challenges



- › Tight Timeframe
- › Manage large number of interfaces on site
- › Different understanding of design boundaries between work packages
- › Difficult to reach key suppliers
- › Language barriers
- › No access to the Network to complete all on load tests
- › Management of key stakeholders
- › Underestimate the project complexity

Design Installation and Commissioning Challenges



Tight Timeframe

- *Compressed program, only one weekend off taken by site personnel*
- *Significant delays in deliveries from overseas impacted on site program*
- *Intense installation work for ABB and Samsung equipment*
- *Design additions after the IFC*

Design Installation and Commissioning Challenges



Difficult to manage multi disciplinary interfaces on site at the same time

- *SCADA,*
- *Telco,*
- *IDS Scheme,*
- *Fire Suppression,*
- *Security,*
- *ABB Equipment,*
- *Equipment Delivery and Installation*
- *Equipment HV testing*
- *Protection Commissioning*
- *Control Schemes*
- *RTU Panel Commissioning*
- *Air Con Installation*

Design Installation and Commissioning Challenges



Different understanding of design boundaries between work packages

- *Additional design required*
- *Additional procurement of panels and equipment required*
- *Additional installation work*
- *Re-work required*
- *Additional testing required*
- *Documentation review and re-issued required*

Design Installation and Commissioning Challenges



Difficult to reach key suppliers

- *All equipment required intense cooperation with the supplier*
- *Most of the suppliers located overseas*
- *Slow responses to key information*

Design Installation and Commissioning Challenges



Language barriers

- *Use of incorrect information due to the formulation of responses*
- *Delivery of plant incomplete*
- *Unable to validate some of the design inputs*

Key Topics


- › Modelling
- › Factory Testing of Complex Control System
- › Inverter/Control System Pre-Commissioning Challenges
- › Custom Training Packages



Modelling

› Modelling – Background


- › Systems focussed historically on islanded / offgrid networks – with varying technology
- › More recently fringe of grid applications appearing
- › ESCRI represents first large grid NEM connected Microgrids
- › Draws requirements for extended functions to be developed and embedded in product
i.e. FFR, FCAS, Network Support



Modelling

› Function Development


› Model Framework overview – Typical for new developments



› Challenges in timeline and interdependency means shift to non-ideal process (next page)

Modelling

› Function Development - Realised



- › Registration timeline leads to parallel of FDS and Model / function development
- › All changes in the design required reflection and validation in all models in parallel – multiple releases.

Modelling



› Modelling – Registration

- › Changes in FDS and design require frequent reissuing of models
- › Model challenges a mix of design validation and implementation issues
- › Following modelling development difficult to isolate model implementation issues from functional changes
- › Model debugging and validation by ABB and partner consultants based on network assumptions which were different to the assumptions used by client consultants
- › Managing a diverse group of stakeholders with diverse drivers
- › Note the VGM model is a new approach - some performance criteria difficult to assess (e.g. Frequency Response requirements)
- › Aligning and benchmarking two modelling packages (PSS/E + PSCAD)

Testing

- › Factory Testing (ABB Darwin)
 - › Complex system simulation
 - › Utilised Darwin grid to simulate NEM
 - › Islanding / Resynchronisation tested successfully with real island
 - › Yorke Peninsula load online
 - › Wattle Point Wind Farm simulated



Testing

- › Factory Testing (ABB Darwin)
 - › Fast Frequency Response (**FFR**) requires utilisation of ‘Virtual Inertia’ within inverters
 - › Parameterised for project specific response – “Keeping the lights on”
 - › ‘**Network Support**’ speed response improvement - <250ms
 - › Novel Frequency Control Ancillary Services (**FCAS**) – developed, incorporated and now standard



Network Response Test Results

Inverter System Pre-Commissioning

- › Multiple ABB factories supplying in to inverter solution
 - › Napier, New Zealand for PCS100 inverters
 - › Trutnov, Czech Republic - Electrical Panels
 - › Assembly in Lobethal, South Australia
- › Lifting/transportation – careful planning with local contractors



Inverter System Pre-Commissioning

ABB

SAMSUNG




A QUANTA SERVICES COMPANY



Control System Pre-Commissioning


› Multiple Communications Interfaces

- › Wattle Point Wind Farm
- › ElectraNet OPSWAN
- › Twelve Inverter/Battery Controllers
- › Existing Dalrymple Substation



Knowledge Sharing Portal

Knowledge Sharing long term data storage – Local Server engineered and supplied
High complexity data acquisition from multiple devices



Training

- › Training Packages for separate audiences
 - › Battery Operator (AGL)
 - › Battery Owner (ElectraNet)
 - › EPC Contract Partner (CPP)



In Summary



- A complex R & D project delivered in an accelerated timeframe
- A complex regulatory environment
- The first grid forming inverter
- Several design and application firsts